



Remove tree

Install an 18" CB with an ADS riser and grated rim and cover

Remove tree

Concrete apron to reduce erosion.

24" frame and grate, CB inlet, approximately 12" down from gutter FL

Flow of water from gutter

Cost for the removal of the trees, dig out base for CB, pour base and riser, backfill around base, grade and pour apron and grade around the new catch basin.
Cost for install complete \$7,500.00