

SECTION 01020

MODIFICATION OF EXISTING FACILITIES AND ORDER OF WORK

PART 1 - GENERAL

1.01 SCOPE

- A. This section covers the care of and works to be done to maintain existing facilities at the site of the work, the requirements for providing traffic control to allow the work in a safe and efficient manner and schedule to do so.
- B. Existing facilities at the site consist of a standard road section that is in need of surface treatment for maintenance purposes. Some of the road sections are bordered with concrete curb / gutter combinations and other distinguishing features that are not scheduled for surface treatment. Care shall be taken to protect those items from damage and or discoloration from surface treatment applied to existing asphalt pavement.

PART 2 - PRODUCTS

- A. Type I Slurry Seal per Caltrans Specifications. Reference Caltrans standard specifications, appendix A and plans.
- B. Fog Seal per Caltrans Specifications. Reference Caltrans standard specifications, appendix B and plans.

PART 3 - EXECUTION

3.01 GENERAL

- A. Provide public notification of the planned activities to complete the work. Provide traffic control per contractors traffic control plan established following Caltrans standards.

3.02 BYPASSING DURING CONSTRUCTION – Not Used

3.03 REMOVAL OF EXISTING STRUCTURES AND EQUIPMENT – Specified Elsewhere

3.04 COORDINATION WITH PLANT OPERATIONS – Not Used

3.05 INTERFERENCE WITH EXISTING LINES

- A. The Contractor will be required to relocate or replace any pipe lines, electric conduits, or other facilities which must be disturbed for new construction work and which are required for plant operation, or make other arrangements satisfactory to the Engineer. Such relocation and replacement may be of temporary type, to be used until work is completed. In the event of accidental damage to existing lines resulting in interruption of service to yard or building lighting circuits or to any other facility which may be needed for use by the Owner prior to the Contractor's next regularly scheduled work period, the Contractor shall repair to the satisfaction of the Engineer such lines prior to stopping work on the day of such damage.

3.06 DEWATERING AND CLEANING OF STRUCTURES AND PIPELINES – Not Used

3.07 ORDER OF WORK

- A. General: The work shall be accomplished in an order that will allow continued traffic flow with the least amount of impact and scheduled as near as possible to the traffic control plan submitted by Contractor.
- B. The intent is Project bid, award, contract and notice to proceed issued ahead of the scheduled work that allows Contractor to plan work within the constructions season on his schedule and to be complete with project prior to October 1, 2016. Once Construction has started, contractor has 30 working days to complete the project.
- C. Basic Requirements:
 - 1. No work may begin on the project site(s) until all contracts, bonds, and insurance coverage documents have been fully executed and a written Notice to Proceed has been issued to the Contractor.
 - 2. When construction has started Contractor shall diligently prosecute the work until completion within 30 working days.

END OF SECTION 01020